

GRAHAM COUNTY
CDBG # 121-22
FAIRGROUNDS ADA IMPROVEMENTS

ADDENDUM NO. 1

BID SCHEDULE

Item No.	Description	Estimated Quantity	Unit	Unit \$	Total \$
	Playground Surface				
1	Subgrade Prep. (Excavation & Compaction)	522	SY		
2	Aggregate Base Course, 4" Thick	522	SY		
3	2" Thick 3,000 PSI Concrete Floor w/ Fiber	4,700	SF		
4	Synthetic Tile Playground Safety Surfacing	4,700	SF		
5	Flat Perforated Grate	1	EA		
6	4" SDR 35 Drain Pipe	80	LF		
7	12" X 12" NDS Drainage Catch Basin	2	EA		
	Sidewalks/Pads				
8	Remove & Dispose of Existing Concrete	28	SF		
9	4" Thick 2,500 PSI Concrete Side	265	SF		
10	6" Thick 2,500 PSI Concrete Pad	60	SF		
11	Sidewalk Scupper	1	EA		
				BID TOTAL	
	Work done 'By OWNER'				
12	Remove & Dispose of Rubber Mulch	4,700	SF		
13	Remove Existing Drinking Fountain	5	EA		
14	Sawcut	10	LF		
15	Install Waterline	14	EA		
16	Install Drinking Fountain Drain Pipe	14	EA		
17	Install Drinking Fountain	14	EA		
18	Install Wall Mounted Drinking Fountain	5	EA		
				OWNER TOTAL	
				PROJECT TOTAL	

Notes:

1. Line item prices shall reflect all expenses including taxes, permit fees, insurance, bonding, and other associated costs incidental to the work.
2. Final payment will be based on unit prices bid multiplied by the actual quantities furnished and accepted.